

SUPERSEDED

Specification (Measurement)

**Transport and Main Roads Specifications
MRS16A Vegetation Protection Works**

April 2012

SUPERSEDED

Copyright



<http://creativecommons.org/licenses/by/3.0/au/>

© State of Queensland (Department of Transport and Main Roads) 2014

Feedback: Please send your feedback regarding this document to: mr.techdocs@tmr.qld.gov.au

Contents

- 1 Introduction1**
- 2 Measurement of work1**
- 2.1 Standard Work Items 1
- 2.2 Work Operations..... 1
 - 2.2.1 *Vegetation protection*1

SUPERSEDED

1 Introduction

This specification applies to vegetation protection work operations associated with road construction. This specification shall be read in conjunction with MRTS16 *General Requirements - Landscape and Revegetation Works*.

This specification shall be read in conjunction with MRS01 *Introduction to Specifications* and other specifications as appropriate.

This specification forms part of the Transport and Main Roads Specifications Manual.

2 Measurement of work

2.1 Standard Work Items

In accordance with the provisions of Clause 2 of MRS01 *Introduction to Specifications*, the standard work items covered by the specification are listed in Table 2.1.

Table 2.1 – Standard Work Items

Standard Work Item No.	Landscape and Revegetation Works Description	Unit of Measurement	Clause Reference in MRTS16A
VEGETATION PROTECTION			
3704	Fencing around vegetation.	m	6
3705	Padding of trees and boarding of drip zones.	lump sum	6

2.2 Work Operations

2.2.1 Vegetation protection

Item 3704 Fencing around vegetation

Work operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of materials and equipment
- c) placement and fixing of vegetation protection
- d) pruning of tree branches and shaping of shrub vegetation
- e) signage of the vegetation protection zone, and
- f) removal and disposal of materials at the end of the construction period.

Item 3705 Padding of trees and boarding of drip zones

Work operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of materials and equipment
- c) placement and fixing of vegetation protection
- d) pruning of tree branches and shaping of shrub vegetation

- e) signage of the vegetation protection zone, and
- f) removal and disposal of materials at the end of the construction period.

SUPERSEDED

SUPERSEDED