

Superseded

Specification (Measurement)

**Transport and Main Roads Specifications
MRS233 Roadway Flood Monitoring Systems**

November 2020

Copyright

© The State of Queensland (Department of Transport and Main Roads) 2020.

Licence



This work is licensed by the State of Queensland (Department of Transport and Main Roads) under a Creative Commons Attribution (CC BY) 4.0 International licence.

CC BY licence summary statement

In essence, you are free to copy, communicate and adapt this work, as long as you attribute the work to the State of Queensland (Department of Transport and Main Roads). To view a copy of this licence, visit: <https://creativecommons.org/licenses/by/4.0/>

Translating and interpreting assistance



The Queensland Government is committed to providing accessible services to Queenslanders from all cultural and linguistic backgrounds. If you have difficulty understanding this publication and need a translator, please call the Translating and Interpreting Service (TIS National) on 13 14 50 and ask them to telephone the Queensland Department of Transport and Main Roads on 13 74 68.

Disclaimer

While every care has been taken in preparing this publication, the State of Queensland accepts no responsibility for decisions or actions taken as a result of any data, information, statement or advice, expressed or implied, contained within. To the best of our knowledge, the content was correct at the time of publishing.

Feedback

Please send your feedback regarding this document to: tmr.techdocs@tmr.qld.gov.au

Contents

- 1 Introduction1**
- 2 Measurement of works1**
 - 2.1 Standard Work Items1
 - 2.2 Work Operations.....2
 - 2.3 Method of measurement of roadway flood monitoring systems.....8
 - 2.4 Supply of materials9

Superseded

1 Introduction

This Specification applies to the requirements for the supply, installation, testing, commissioning and maintenance handover documentation (including the provision for operator training) of Roadway Flood Monitoring Systems.

This Specification shall be read in conjunction with MRS01 *Introduction to Specifications*, MRS263 *Standalone Solar (PV) Power Systems* and other Specifications as appropriate.

This Specification forms part of the Transport and Main Roads Specifications Manual.

2 Measurement of works

2.1 Standard Work Items

In accordance with the provisions of Clause 2 of MRS01 *Introduction to Specifications*, the Standard Work Items covered by this Specification are listed in Table 2.1.

For Standard Work Items relating to Solar Power and Battery power, refer to MRS263 *Standalone Solar (PV) Power Systems*. For Standard Work Items for Mains Connection, refer to MRS210 *Provision of Mains Power*.

Table 2.1 – Standard Work Items

Standard Item No.	Description	Unit of measurement
Roadway Flood Monitoring System		
64701	Supply of [<i>tilt</i> <i>fixed</i>] pole support structure with approved [<i>fixed</i> <i>relocatable</i>] footing assembly as detailed on referenced approved drawings	each
64702	Installation of [<i>tilt</i> <i>fixed</i>] pole support structure with approved [<i>fixed</i> <i>relocatable</i>] footing assembly as detailed on referenced approved drawings	each
64703	Supply and Installation of [<i>tilt</i> <i>fixed</i>] pole support structure with approved [<i>fixed</i> <i>relocatable</i>] footing assembly as detailed on referenced approved drawings	each
64704	Supply of all-weather pole mounted equipment enclosure fixed to the support structure to house all relevant Flood Monitoring electronic equipment including routers, radio equipment, digital input/output equipment, data logging and telecommunication equipment	each
64705	Installation of all-weather pole mounted equipment enclosure fixed to the support structure to house all relevant Flood Monitoring electronic equipment including routers, radio equipment, digital input/output equipment, data logging and telecommunication equipment	each
64706	Supply and installation of all-weather pole mounted equipment enclosure fixed to the support structure to house all relevant Flood Monitoring electronic equipment including routers, radio equipment, digital input/output equipment, data logging and telecommunication equipment	each
64710	Supply of [<i>Radar</i> <i>Ultrasonic</i> <i>Conductive probe</i> <i>Gas bubbler</i>] Flood Level sensor, or other approved types	each

Standard Item No.	Description	Unit of measurement
64711	Installation of [<i>Radar</i> <i>Ultrasonic</i> <i>Conductive probe</i> <i>Gas bubbler</i>] Flood Level sensor, or other approved types	each
64712	Supply and installation of [<i>Radar</i> <i>Ultrasonic</i> <i>Conductive probe</i> <i>Gas bubbler</i>] Flood Level sensor, or other approved types	each
64713	Supply of integrated Telecommunications link for backhaul of flood height data to head end monitoring site, as well as any pole mounted antenna systems	each
64714	Installation of integrated Telecommunications link for backhaul of flood height data to head end monitoring site, as well as any pole mounted antenna systems	each
64715	Supply and installation of integrated Telecommunications link for backhaul of flood height data to head end monitoring site, as well as any pole mounted antenna systems	each
Ancillary / optional items		
64751	Supply of approved local Roadway Flood warning signage as per TC 1768, and any related wireless or cable system to connect this signage to the nearby roadway flood monitoring equipment	each
64752	Installation of approved local Roadway Flood warning signage as per TC 1768, and any related wireless or cable system to connect this signage to the nearby roadway flood monitoring equipment	each
64753	Supply and installation of approved local Roadway Flood warning signage as per TC 1768, and any related wireless or cable system to connect this signage to the nearby roadway flood monitoring equipment	each
64754	Supply of pole mounted camera equipment for roadway flood image capture back to a remote head end with or without infrared illuminator for night time roadway illumination	each
64755	Installation of pole mounted camera equipment for roadway flood image capture back to a remote head end with or without infrared illuminator for night time roadway illumination	each
64756	Supply and installation of pole mounted camera equipment for roadway flood image capture back to a remote head end with or without infrared illuminator for night time roadway illumination	each
Removal of existing roadway flood monitoring system		
64791	Removal of roadway flood monitoring equipment for re-use	each
64792	Removal of roadway flood monitoring equipment for disposal	each

2.2 Work Operations

Item 64701 Supply of [*tilt* | *fixed*] pole support structure with approved [*fixed* | *relocatable*] footing assembly as detailed on referenced approved drawings

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply and fabrication of as appropriate

- c) for fixed base poles, supply and installation of eyebolt and bushing for aerial supply if appropriate
- d) for relocatable poles, supply of slip base mount, shear washer and clamping bolts, and
- e) supply of all fixing bolts, nuts and washers as appropriate.

Item 64702 Installation of [tilt | fixed] pole support structure with approved [fixed | relocatable] footing assembly as detailed on referenced approved drawings

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) excavation for footing
- c) disposal of excavated material
- d) provision of formwork, where necessary
- e) installation of base mounts, shear washer, clamping bolts and nuts and cable clamping blocks
- f) installation of cable clamping blocks as appropriate
- g) Installation and termination of all internal cabling
- h) Installation of pole, as appropriate
- i) installation and termination of cabling from base connectors to sensors including supply and installation of pit junction box, if applicable, and
- j) testing of installation.

Item 64703 Supply and Installation of [tilt | fixed] pole support structure with approved [fixed | relocatable] footing assembly as detailed on referenced approved drawings

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply and fabrication of as appropriate
- c) excavation for footing
- d) disposal of excavated material
- e) provision of formwork, where necessary
- f) supply and installation of eyebolt and bushing for aerial supply if appropriate
- g) supply and installation of slip base mount, shear washer and clamping bolts
- h) supply and installation of base mounts, shear washer, clamping bolts and nuts and cable clamping blocks
- i) supply and installation of cable clamping blocks as appropriate
- j) supply and installation and termination of all internal cabling
- k) supply and installation of pole, as appropriate

- l) supply and installation and termination of cabling from base connectors to sensors including supply and installation of pit junction box, if applicable
- m) supply and installation of all fixing bolts, nuts and washers as appropriate
- n) stripping formwork, reinstatement of soil cover and general making good on site, and
- o) testing of installation.

Item 64704 Supply of all-weather pole mounted equipment enclosure fixed to the support structure to house all relevant Flood Monitoring electronic equipment including routers, radio equipment, digital input/output equipment, data logging and telecommunication equipment

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*, and
- b) supply of approved telecommunications enclosure.

Item 64705 Installation of all-weather pole mounted equipment enclosure fixed to the support structure to house all relevant Flood Monitoring electronic equipment including routers, radio equipment, digital input/output equipment, data logging and telecommunication equipment

Work Operations incorporated in the above item include:

Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*

- a) installation of the approved telecommunications enclosure, and
- b) installation and termination of all internal cabling.

Item 64706 Supply and installation of all-weather pole mounted equipment enclosure fixed to the support structure to house all relevant Flood Monitoring electronic equipment including routers, radio equipment, digital input/output equipment, data logging and telecommunication equipment

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of approved telecommunications enclosure
- c) installation of the approved telecommunications enclosure, and
- d) installation and termination of all internal cabling.

Item 64710 Supply of [Radar | Ultrasonic | Conductive probe | Gas bubbler] Flood Level sensor, or other approved types

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*, and
- b) supply of flood level sensor as appropriate.

Item 64711 Installation of [Radar | Ultrasonic | Conductive probe | Gas bubbler] Flood Level sensor, or other approved types

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) installation of flood level sensor to manufacturer's instructions and Transport and Main Roads guidelines, and
- c) testing of flood level sensor.

Item 64712 Supply and installation of [Radar | Ultrasonic | Conductive probe | Gas bubbler] Flood Level sensor, or other approved types

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply and installation of flood level sensor to manufacturer's instructions and contract requirements, and
- c) testing of flood level sensor.

Item 64713 Supply of integrated Telecommunications link for backhaul of flood height data to head end monitoring site, as well as any pole mounted antenna systems

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of copper or fibre communication, as appropriate
- c) supply of 3G/NextG/4G communication systems and accessories, as appropriate
- d) supply of satellite communication systems and accessories, as appropriate
- e) supply of repeater sites and accessories, as appropriate, and
- f) supply of pole mounted antenna systems as appropriate.

Item 64714 Installation of integrated Telecommunications link for backhaul of flood height data to head end monitoring site, as well as any pole mounted antenna systems

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) installation of copper or fibre communication, as appropriate
- c) installation of 3G/NextG/4G communication systems and accessories as appropriate
- d) installation of satellite communication systems and accessories, as appropriate
- e) installation of repeater sites and accessories as appropriate
- f) installation of pole mounted antenna systems as appropriate, and
- g) testing of telecommunication link between head end monitoring site, flood monitoring site, cameras and signage as appropriate.

Item 64715 Supply and installation of integrated Telecommunications link for backhaul of flood height data to head end monitoring site, as well as any pole mounted antenna systems

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply and installation of copper or fibre communication, as appropriate
- c) supply and installation of 3G/NextG/4G communication systems and accessories, as appropriate
- d) supply and installation of satellite communication systems and accessories, as appropriate
- e) supply and installation of repeater sites and accessories, as appropriate
- f) supply and installation of pole mounted antenna systems as appropriate, and
- g) testing of telecommunication link between head end monitoring site, flood monitoring site, cameras and signage as appropriate.

Item 64751 Supply of approved local Roadway Flood warning signage as per TC 1768, and any related wireless or cable system to connect this signage to the nearby roadway flood monitoring equipment

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*, and
- b) Supply of TC 1768 Flood warning signage and accessories.

Item 64752 Installation of approved local Roadway Flood warning signage as per TC 1768, and any related wireless or cable system to connect this signage to the nearby roadway flood monitoring equipment

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) excavation for footing
- c) disposal of excavated material
- d) provision of formwork, where necessary
- e) installation of TC 1768 Flood warning signage and accessories
- f) installation of conduit to electrical and/or communications pit, as appropriate
- g) installation of antennae for wireless communication as appropriate
- h) installation of binding concrete to MRTS 70
- i) pouring, curing and finishing of concrete to MRTS 70, and
- j) stripping formwork, reinstatement of soil cover and general making good on site.

Item 64753 Supply and installation of approved local Roadway Flood warning signage as per TC 1768, and any related wireless or cable system to connect this signage to the nearby roadway flood monitoring equipment

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) excavation for footing
- c) disposal of excavated material
- d) provision of formwork, where necessary
- e) supply and Installation of TC 1768 Flood warning signage and accessories
- f) supply and installation of antenna for wireless communication, as appropriate
- g) supply and installation of conduit to electrical and/or communications pit, as appropriate
- h) supply and Installation of binding concrete to MRTS 70
- i) pouring, curing and finishing of concrete to MRTS 70, and
- j) stripping formwork, reinstatement of soil cover and general making good on site.

Item 64754 Supply of pole mounted camera equipment for roadway flood image capture back to a remote head end with or without infrared illuminator for night time roadway illumination

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of camera and associated equipment, and
- c) supply of camera pole as appropriate.

Item 64755 Installation of pole mounted camera equipment for roadway flood image capture back to a remote head end with or without infrared illuminator for night time roadway illumination

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) installation of camera pole as appropriate, and
- c) cabling and termination of power and communication cables to camera and associated equipment.

Item 64756 Supply and installation of pole mounted camera equipment for roadway flood image capture back to a remote head end with or without infrared illuminator for night time roadway illumination

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply and Installation of camera pole as appropriate

- c) supply and installation of camera and associated equipment, and
- d) cabling and termination of power and communication cables to camera and associated equipment.

Item 64791 Removal of roadway flood monitoring equipment for re-use

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) disconnection of Electrical Supply including termination and “making safe” of supply cable, as appropriate
- c) disconnection of Telecommunications connection, as appropriate
- d) removal of flood monitoring equipment and supporting pole and associated cabinet enclosure, as appropriate
- e) reinstatement of soil cover and general making good on site, and
- f) transport of all components to Principal’s storage facility or designated site storage area for reuse.

Item 64792 Removal of roadway flood monitoring equipment for disposal

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) disconnection of Electrical Supply including termination and “making safe” of supply cable
- c) disconnection of Telecommunications connection
- d) removal of VSL/LC and supporting pole and associated cabinet enclosure
- e) reinstatement of soil cover and general making good on site, and
- f) transport of all components and disposal.

2.3 Method of measurement of roadway flood monitoring systems

This Specification provides Standard Work Items for:

- a) supply only
- b) installation only
- c) supply and installation, or
- d) lease arrangements for hardware and/or related support services and maintenance of Roadway Flood monitoring Systems.

Any combination of Standard Work Items relating to these methods of measurement may be used in the Schedule of Rates. However, where a Standard Work Item for supply and installation of a particular component or group of components is included in the Schedule of Rates, no supply only nor installation only Standard Work Item shall also apply to that component or group of components, as applicable.

2.4 Supply of materials

Any materials to be supplied by the Principal will be as stated in the Principal Supplied Material List, Form C6827. All other material shall be supplied by the Contractor.

The responsibility for transport to the Site of materials supplied by the Principal shall be as stated in the Principal Supplied Material List, Form C6827. Transport to the Site of all other materials shall be the responsibility of the Contractor.

Superseded

Superseded